

## **G-90**

This structure is a reinforced concrete, gated spillway with discharge controlled by two stem operated, vertical lift gates, discharging into a reinforced concrete box culvert. Operation of the gates is manually controlled in accordance with the established operational criteria. The structure is located on a channel connected to Lake June-in-Winter; it discharged into Jack Creek.

### **PURPOSE**

This structure is the main outlet from Lake June-in-Winter. It is operated in conjunction with the outlet to Lake Francis (G-91). The latter discharges into Lake Francis, the natural outlet of which is Jack Creek.

### **OPERATION**

Most discharges will be made through the outlet to Lake Francis.

Whenever Lake June is above schedule, required discharges will be calculated to bring the lake to the regulation schedule within two weeks. When the releases through the outlet to Lake Francis will not meet this criterion, releases will be made through the G-90 structure. The maximum gate opening will normally be limited to two gates at 1.0 feet.

Gate opening of 1.5 feet on both gates can be made for periods of eight hours. If larger releases are required to bring Lake June down to schedule, coordination with the Highlands County Engineer and visual surveillance of the outlet channel is required.

### **FLOOD DISCHARGE CHARACTERISTICS**

	*Maximum Allowable	Design
Discharge Rate	<u>375 cfs</u>	<u>760 cfs</u>
		Indeterminate % SPF
Headwater Elevation	<u>74.25 feet</u>	Unknown
Tailwater Elevation	<u>69.74 feet</u>	Unknown
Type Discharge	<u>Controlled, submerged</u>	Unknown

\*The values are for non-damaging conditions in the downstream channel, based on measurements taken before stabilization of the downstream stage. The discharge for stabilized conditions would be slightly less

**DESCRIPTION OF STRUCTURE**Type reinforced concrete, gated structure

Weir Crest

Lower Weir

Net Length 14.0 feetElevation 65.37 feet

Upper Weir

Net Length 12.0 feetElevation 74.0 feetService Bridge Elevation 17 feetWater level which will bypass structure 77.0 feet

Gates

Number 2Size 8.0 ft. high by 8.0 ft. wideType Vertical lift gatesBottom Elevation of gates, full open: 73.0 feetTop Elevation of gates, full closed: 74.5 feetControl: Manual

Lifting mechanism

Normal power source Manual or portable generatorPowered electric motorType Hoist: Pedestal mounted crank

**ACCESS:** West about 3 miles on SR 621 from U.S. 27 and north about 1 1/2 miles via county road on east bank of Jack Creek.

**HYDRAULIC & HYDROLOGIC MEASUREMENTS**Water Level On-site headwater and tailwater staff gauges onlyGate Position Recorder None**DEWATERING FACILITIES** None