

STRUCTURE 175

This structure is a triple-barreled, reinforced concrete pipe culvert, located on the Levee 31W borrow canal about 1 and 1/2 miles north of State Road 27. Control is effected by manually operated sluice gates mounted on a reinforced concrete head structure.

PURPOSE

This structure is closed under IOP.

OPERATION

This structure will be operated as directed by the Corps of Engineers.

FLOOD DISCHARGE CHARACTERISTICS

	Design	Standard Project Flood
Discharge Rate	<u>500</u> cfs	<u>500</u> cfs
	<u>40</u> % SPF	<u>100</u> % SPF
Headwater Elevation	<u>5.0*</u> feet	<u>6.0*</u> feet
Tailwater Elevation	<u>4.5*</u> feet	<u>5.5*</u> feet
Type Discharge	controlled <u>submerged</u>	<u>submerged</u>

*Some question of stages because later Corps' studies of C-111 raised the stage below S-18C 0.7 feet above the stage given in studies which gave stages shown for S-175.

DESCRIPTION OF STRUCTURE

Type	<u>Reinforced concrete pipe culvert with upstream control</u>	
Number of barrels	<u>3</u>	
Size of barrel	<u>84 inches</u>	
Length of barrel	<u>56 feet</u>	
Flow line elevation	<u>-5.0 feet</u>	
Service bridge elevation	<u>14.0 feet</u>	
Water level which will by-pass structure	<u>9.0</u>	
Control Structure	<u>reinforced concrete headwall</u>	
Gates		
Number	<u>3</u>	
Type	<u>sluice gate mounted on structure at upstream end of culvert</u>	

Revised 4/07/03

Size 84" in diameter

Control automatic, on-site upstream control, remote control by C&CS

Lifting Mechanism

Type pedestal mounted, manually operated hoist

ACCESS: from U.S. Highway 27 via access road on east berm of L-31W Borrow Canal

HYDRAULIC AND HYDROLOGIC MEASUREMENTS

Water Level On-site digital recorder at upstream and downstream

Gate Position Recorder On-site digital recorder

DEWATERING FACILITIES None