

STRUCTURE 21

This structure is a reinforced concrete, gated spillway with discharge controlled by three cable operated, vertical lift gates. Operation of the gates is automatically controlled so that the gate hydraulic operating system opens or closes the gates in accordance with the operational criteria. The structure is located near the mouth of Canal 1 at its junction with Levee 31E and about 3500 feet from the shore of Biscayne Bay.

PURPOSE

This structure maintains optimum water control stages upstream in Canal 1; it passes the design flood (40 percent of the Standard Project Flood) without exceeding upstream flood design stage, and restricts downstream flood stages and discharge velocities to non-damaging levels; and it prevents saline intrusion during periods of high flood tides.

OPERATION

This structure will be operated to maintain an optimum headwater elevation which varies seasonally from a low of 2.0 feet during the dry season to a maximum of 2.4 feet, during the flood season, when sufficient water is available to maintain this level. The automatic controls in the gates function as follows:

High Range

When the headwater elevation rises to 2.4 feet, the gates will open at six inches per minute.

When the headwater elevation rises or falls to 1.9 feet, the gates will become stationary;

When the headwater elevation falls to 1.5 feet, the gates will close at six inches per minute.

Low Range

This setting is used only when the fall is unusually wet. Otherwise, the flood season setting is used throughout the year. If the dry season setting is used, it functions as follows:

When the headwater elevation rises to 2.0 feet, the gates will open at six inches per minute;

When the headwater elevation rises or falls to 1.5 feet, the gates will become stationary;

When the headwater elevation falls to 1.0 feet, the gates will close.

The selection of operational range will be based on the basin condition.

Salinity Regulation

In addition to maintaining optimum upstream fresh water control, as described above under Flood Control Regulation, the automatic controls on this structure have an over-riding control which closes the gates, regardless of the upstream water level in the rare event of a high flood tide, whenever the differential between the head and tailwater pool elevations reaches 0.2 feet.

FLOOD DISCHARGE CHARACTERISTICS

	Design	Standard Project Flood
Discharge Rate	<u>2560</u> cfs <u>40%</u> SPF	<u>4300</u> cfs <u>100%</u> SPF
Headwater Elevation	<u>1.9</u> feet	<u>2.8</u> feet
Tailwater Elevation	<u>1.4</u> feet	<u>2.0</u> feet
Type Discharge	uncontrolled <u>submerged</u>	uncontrolled <u>submerged</u>
Estimated Maximum Hurricane Tide	<u>15.6</u> feet m.s.l.	

DESCRIPTION OF STRUCTURE

Type fixed crest, reinforced concrete gated spillway

Weir Crest

Net Length 81.0 feet

Elevation -6.5 feet

Service bridge elevation 5.3 feet

Water level elevation which will by-pass structure 8.0 feet

DEWATERING FACILITIES

Storage	<u>needles at HomesteadField Station, beams at West Palm Beach</u> <u>Field Station</u>
Type	<u>needle beams and vertical aluminum needles</u>
Size and number (per bay)	
Upstream & Downstream	
Number	<u>1 beam; needles, 6 @ 4', 1 @ 3' wide</u>
Size	<u>beam 24WF160, length 28' -11"</u> <u>needles 20' long</u>