

STRUCTURE 58

This structure is a double-barreled corrugated metal pipe culvert, with discharge controlled by stem operated, vertical lift gates. Operation of the gates is manually in accordance with the seasonal operational criteria. The structure is located on Canal 32 about 3700 feet downstream from Trout Lake.

PURPOSE

This structure maintains optimum upstream water control stages in Canal 32 and in Lakes Alligator, Lizzie, Coon, Center and Trout; it passes the design flood (30% of the Standard Project Flood) without exceeding the upstream flood design stage, and it restricts downstream flood stages and channel velocities to non-damaging levels; it prevents overtopping of the structure by breaking waves from Lake Trout during the design storm and wind tide; it prevents overtopping of the structure during the Standard Project Flood and hurricane wind tide, though it will be overtopped by breaking waves under such conditions; and it passes sufficient discharge during low-flow periods to maintain downstream stages and irrigation demands.

OPERATION

This structure is operated in accordance with the Lake Alligator Regulation Schedule. This schedule, which ranges between elevations 62.0 and 64.0, indicates the desirable water level throughout the year. If the level is above the prescribed level, flood operation is followed; if the level is below the prescribed level, low-water operation is followed. The operation is also dependent on hydraulic and structural limitations of the structure.

Flood Control Operation

Both S-60 and S-58 discharge from Lake Alligator, consequently discharges from both structures must be considered in establishing release schedules. When the lake level is within 0.5 foot of the prescribed level, a release schedule, based on forecasted inflow, will be established to return the lake to that level within 15 days.

When the lake stage is over 0.5 foot from the prescribed level, maximum releases, subject to hydraulic and structural limitation, will be made.

Low-Water Operation

Whenever the lake level is below the prescribed level, no releases will be made.

Structural Limitations

The maximum water level drop across the structure will be 4 feet.

The maximum headwater elevation will be 64.0 feet.

FLOOD DISCHARGE CHARACTERISTICS

	Design		Standard Project Flood
	Lower Profile*	Peak Stage*	
Discharge Rate	<u>105</u> cfs <u>30</u> %SPF	<u>160</u> cfs <u>30</u> %SPF	<u>14.0</u> cfs <u>100</u> %SPF
Headwater Elevation			
Static	<u>62.9</u> feet	<u>64.8</u> feet	<u>67.4</u> feet
Wind Tide	<u> </u> feet	<u>65.5</u> feet	<u>67.9</u> feet
Wind Tide plus Breaking Wave Height	<u> </u> feet	<u>69.1</u> feet	<u>75.8</u> feet
Tailwater Elevation	<u>61.3</u> feet	<u>63.0</u> feet	<u>66.7</u> feet
Type Discharge	<u>Controlled Submerged</u>	<u>Controlled Submerged</u>	<u>Uncontrolled Submerged</u>

*Peak Stage is based on lake operation for design flood which allows 2.0 feet of storage above historic average levels. Lower Profile is based on no rise in lake levels from historic average. Actual operation will probably be close to Lower Profile for the design flood.

DESCRIPTION OF STRUCTURE

Type	<u>reinforced concrete culvert with upstream control</u>
Number of barrels	<u>2</u>
Size of barrels	<u>54 inch diameter</u>
Length of barrels	<u>70 feet</u>
Flow line elevation	<u>54.5 feet</u>
Service bridge elevation	<u>70.0 feet</u>
Water Level which will by-pass structure	<u>70.0 feet</u>

GATES

Number 2
Type vertical slide gates
Size 54 inch diameter
Control manual
Lifting Mechanism
Type pedestal mounted electric motor
Source of Power Commercial electricity
Auxiliary Power LP gas engine driven generator

ACCESS: from Nova Road via access road on west (left) side C-32

HYDRAULIC AND HYDROLOGIC MEASUREMENTS

Water Level Remote digital (upstream and downstream) recorders
Gate Position Recorder Remote digital recorders
Other _____

DEWATERING FACILITIES (per barrel) None