# STRUCTURE 79 Franklin Lock

This structure is a reinforced concrete, gated spillway with discharge controlled by eight chain operated, vertical lift gates and a reinforced concrete lock with two sets of sector gates. Operation of one of the spillway gates is automatically controlled so that the gate is operated in accordance with the operational criteria. The structure is located on Canal 43 (the Caloosahatchee River) about 30 miles east of S-78 and about 7 miles from tidewater.

#### **PURPOSE**

The structure maintains optimum upstream water control stage of 3.0 in Canal 43; it passes the design flood (30% of the Standard Project Flood) without exceeding the upstream flood design stage; and restricts downstream flood stages and channel velocities to non-damaging levels and to prevent saline intrusion during high tide and low upstream water surface elevations.

#### SPILLWAY OPERATING CRITERIA

This structure is operated and maintained by the U.S. Corps of Engineers so as to pass the base flow automatically. Larger flows are controlled by all of the gates.

When the headwater elevation rises to 3.2 feet, the gate begins to open at 6 inches per minute, with a maximum of 12.0 ft. opening.

When the headwater elevation rises or falls to elevation 3.0, the gate becomes stationary.

When the headwater elevation falls to 2.8, the gate begins to close at 6 inches per minute.

The two end gates are equipped with skimmer gates which can be manually operated to remove debris.

If the flow cannot be passed by the manually controlled gate, other gates with manual controls are to be opened.

### FLOOD DISCHARGE CHARACTERISTICS

	Design Stand	dard Project Flood
Discharge Rate	<u>28,900</u> cfs	cfs
		_100 % SPF
Headwater Elevation	4.4 feet	<u>8.4</u> feet
Tailwater Elevation	3.9 feet	3.0 to 7.9 feet

Type Discharge \_\_\_\_\_

#### **DESCRIPTION OF SPILLWAY STRUCTURE**

Type <u>reinforced concrete, gated spillway</u>

Weir Crest

Net Length 304.0 feet

Elevation -15.0 feet

Service Bridge Elevation 10.5 feet

Water Level which will by-pass structure 10.5 feet

Gates

Number 8

Size <u>19.2 ft. high by 38.8 ft. wide</u>

Type <u>vertical slide gates</u>

Bottom elevation of gates, full open <u>5.4</u> feet

Top elevation of gates, full closed 4.2 feet

Control On-site automatic on #4 gate, all others manual

Lifting Mechanism

Normal power source commercial electricity

Emergency power source gasoline motor driven generator

Type Hoist traveling crane with electric motor driven drums and

chain lifts

**ACCESS:** from SR 80A via access road, the south end of which is about 1,500 feet west of

intersection of roads 80 and 80A

## HYDRAULIC AND HYDROLOGIC MEASUREMENTS

Water Level On-site, dual recorder

Gate Position Recorder On-site

## **DEWATERING FACILITIES**

Storage <u>U.S. Corps of Engineers</u>

Type <u>Bulkhead gates</u>

Size and Number (per bay) 10

39'-9" long X 4'-6" high

2'-10"+ wide

Each spillway gate section can be dewatered by using ten bulkheads. The bulkheads can be stacked on top of each other to a maximum of 5 on the upstream and 5 on the downstream side. Each bulkhead is 4'-5" high, 2'-10" wide and 39'-9" long.